



WOOD RAIL FENCE

SCALE 1" = 2'

WETLAND MITIGATION AREA

SCALE 1" = 20'

PLANT MATERIAL LIST

QTY	BOTANICAL NAME	COMMON NAME	SIZE & SPACING
A	G3	RED DOGWOOD	1 GAL. - 5 O.C. CLUMPED
B	52	BLAUF TINKERRY	1 GAL. - 5 O.C. CLUMPED
C	47	Physocarpus opulifolius	1 GAL. - 5 O.C. CLUMPED
D	55	GR. N. BUSH	1 GAL. - 5 O.C. CLUMPED
E	50	GR. N. BUSH	PLUS - RANDOM INTERVAL

ELEVATION

SCALE 1" = 2'

SHEET NOTES:

DRAWING IS DIAGRAMMATIC AND SHOWS INTENT. ACTUAL ON THE GROUND PLANTING LOCATIONS WILL BE DETERMINED BY THE PROJECT BIOLOGIST.

MITIGATION AREAS SHALL BE CLEARED AND GRADED AND THIS MATERIAL SHALL BE HAILED OFF SITE. AREA TO BE CLEARED AND GRADED IS 4866 S.F. FOR THE WETLAND AREA AND 1044 S.F. FOR THE WALKING PATH.

COUNTY TO FLAG WETLAND CLEARING LIMITS PRIOR TO CONSTRUCTION. ALL EXCAVATED MATERIAL SHALL BE HAILED OFF SITE. THE VOLUME OF CUT FOLLOWING CLEARING AND GRABBING IS 100 C.Y.

PLANT SPECIES, QUANTITIES, AND SIZE MUST BE PROVIDED AS SPECIFIED. ANY SUBSTITUTIONS MUST BE APPROVED BY THE PROJECT BIOLOGIST.

ALL COMMERCIALLY ACQUIRED ROOTED PLANTS ARE TO BE CONTAINERIZED OR BARE-ROOT.

ALL PLANTING MATERIALS SHALL BE HEALTHY, SOUND, VIGOROUS OF GROWTH, FREE OF ANY DEFECTS, DISEASES AND ANY FORM OF INFESTATIONS.

ALL PLANTING WILL BE RANDOM (HAND Laid) NOT BY STRING LINES TO ENHANCE A NATURAL PATTERN OF GROWTH.

TREE AND SHRUB PLANTING SHALL BE PER DETAILS.

PLANTING BACKFILL SOIL SHALL BE LOCAL SOIL TO THE PLANTING AREA.

CONTROL POINTS

No.	By	Date

REVISIONS

No.	By	Date	Description

DESIGNED:	BLB
DRAWN:	BLB
CHECKER:	RED
CRP NO.:	1559
DATE:	01/08/08

KITSAP COUNTY DEPT. OF PUBLIC WORKS
 614 DIVISION STREET SE, SUITE 206
 BELLEVILLE, WA 98241
 TEL: (360) 537-5777 FAX: (360) 537-4867

HOOD CANAL DRIVE NE WETLAND MITIGATION
 KITSAP COUNTY, WASHINGTON
 SECTION 20, TOWNSHIP 28 NORTH, RANGE 2 EAST, W.M.